

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-24061-00-00
Spot: NENENW Sec/Twnshp/Rge: 3-19S-21W
4871 feet from S Section Line, 2897 feet from E Section Line
Lease Name: MOORE Well #: 1-3
County: NESS Total Vertical Depth: 4402 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4130		WITH 2 SX CMT
CIBP		4351		WITH 2 SX CMT
DVT	5.5	2386		WITH 355 SX CMT
PROD	5.5	4399	0	WITH 150 SX CMT
SURF	8.625	226		WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/18/2018 2:00 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: SCOTT CORSAIR Company: AMERICAN WARRIOR Phone: (785) 398-2270

Proposed Plugging Method: PUMP 200# HULLS IN FIRST BATCH CMT THEN CMT TO SURFACE FROM 2297'. FILL BACKSIDE WITH CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: PARTIAL
Date/Time Plugging Completed: 06/19/2018 11:00 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PUMPED 290 SX CMT & 200# HULLS IN FIRST OF CMT. MAXIMUM PRESSURE 1000#. CASING WENT ON A VACUUM. TIED ONTO BACKSIDE & MIXED 5 SX CMT. PRESSURED TO 300#. 6/19/18: FOUND CMT AT 920'. TIED ONTO CASING & PUMPED 85 SX CMT. CASING PRESSURED UP & STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
4283	4289	CSG	
4187	4257	CSG	

INVOICED
JUL 12 2018

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01 RECEIVED
JUN 25 2018
KCC DODGE CITY

Signed Michael Maier
(TECHNICIAN)