

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-145-20526-00-00
Spot: SWNW Sec/Twnshp/Rge: 7-20S-20W
3271 feet from S Section Line, 4612 feet from E Section Line
Lease Name: SMITH Well #: 1
County: PAWNEE Total Vertical Depth: 4378 feet

Operator License No.: 4058 String Size Depth (ft) Pulled (ft) Comments
Op Name: AMERICAN WARRIOR, INC. PROD 5.5 4369 0 WITH 100 SX CMT
Address: PO BOX 399 SURF 8.625 461 WITH 250 SX CMT
GARDEN CITY, KS 67846

Well Type: OIL UIC Docket No: Date/Time to Plug: 06/11/2018 3:30 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: SCOTT CORSAIR Company: AMERICAN WARRIOR Phone: (785) 398-2270

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 50 SX CMT & 200# HULLS. PULL TBG TO 3100' & SPOT 75 SX CMT & 300# HULLS. LET CMT SET. PRESSURE CASING TO 500#. IF HOLDS PERFORATE AT 1480' 50 SX CMT 25 WITH HULLS & 25 WITHOUT HULLS. PERFORATE AT 480' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: PARTIAL
Date/Time Plugging Completed: 06/12/2018 4:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4374' & MIXED 50 SX CMT & 200# HULLS. PULL TBG TO 3100' & MIXED 75 SX CMT & 300# HULLS. SDON. 6/13/18: PERFORATED AT 1450' & SPOTTED 40 SX CMT 20 WITH HULLS & 20 WITHOUT HULLS. PERFORATED AT 454'. MIXED 110 SX CMT. CMT CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4372	4378	CSG	

INVOICED

JUL 12 2018

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed

Michael Maier

(TECHNICIAN)

RECEIVED
JUN 19 2018
KCC DODGE CITY

MD

Form CP-2/3

KMS