

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-055-20352-00-01
Spot: SESESENW Sec/Twnshp/Rge: 35-25S-31W
2827 feet from S Section Line, 2655 feet from E Section Line
Lease Name: BEACH Well #: 1-35
County: FINNEY Total Vertical Depth: 5050 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1670		
CIBP		4527		WITH 2 SX CMT
DVT		3249		WITH 250 SX CMT
PROD	5.5	5050	0	WITH 400 SX CMT
SURF	8.625	1622		WITH 750 SX CMT

Well Type: SWD UIC Docket No: D26645.0 Date/Time to Plug: 06/26/2018 8:30 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JOSE REYES Company: AMERICAN WARRIOR Phone: (620) 275-2963

Proposed Plugging Method: SET CIBP @ 4527' WITH 2 SX CMT. PRESSURE TEST CASING. PERFORATE AT 1672' CIRCULATE CMT TO SURFACE IN & OUT 5 1/2".

Plugging Proposal Received By: LARRY HARRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/26/2018 1:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 4527' WITH 2 SX CMT. CIBP @ 1670' (TO ISOLATE LEAKS IN SQUEEZED CHASE PERFS). TEST CASING TO 500#. HOLDING. PERFORATE 4 HOLES AT 1650'. INJECTION RATE 3 BPM @ 250#. PUMP 400 SX CMT VIA 5 1/2" CASING THROUGH PERFS & CIRCULATE CMT TO SURFACE LEAVING THE 5 1/2" CASING & 5 1/2" X 8 5/8" ANNULUS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
4577	4594		

INVOICED


JUL 12 2018

Remarks: **COMPLIANCE ISSUE: FAILED MIT** USED 60/40 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

RECEIVED
JUN 29 2018
KCC DODGE CITY

Form CP-2/3

Handwritten initials