

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-26857-00-00
Spot: NENWSWNE Sec/Twnshp/Rge: 7-13S-19W
1595 feet from N Section Line, 2281 feet from E Section Line
Lease Name: SLAUGHTER Well #: 1-7
County: ELLIS Total Vertical Depth: 3925 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 5.5 | 3922 | | 130 SX |
| SURF | 8.678 | 218 | | 150 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/04/2018 10:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: OCTAVIO D MORALES Company: AMERICAN WARRIOR, INC. DBA Phone: (620) 275-2963

Proposed Plugging Method: Port Collar at 1483' w/225 sx cement. Did not circulate.
Top of cement at 590'. Perforated and cemented to surface with 175 sx cement.
Production perforations: 3514' - 3524'.
Ordered 250 sx 60/40 pozmix 4% gel cement, 1500 # gel and 200 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/04/2018 1:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 3500'. Swift Services pumped 1500 # gel followed by 50 sx cement w/200 # hulls Pulled tubing to 1525' and pumped 150 sx cement. Cement circulated. PTOH. Topped 5 1/2" casing off with 25 sx cement. Backside full of cement.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3514 | 3524 | | |


INVOICED
JUL 12 2018

Remarks: SWIFT SERVICES TICKET # 27296

Plugged through: TBG

District: 04

Signed



Received
KANSAS CORPORATION COMMISSION

(TECHNICIAN)

CM

JUN 05 2018

JUN 25 2018

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3