



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 6 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Monte Chadd of Petroleum, Inc. has this date requested permission to plug the following described well:

Mr. Petroleum Inc. guarantees payment of the plugging fee.

Operator's full Name: Petroleum Inc.

Complete Address: R. R. # 2, Great Bend, Kansas 67530

Lease Name: Hulme "D" Well No. # 1

Location: SE NW NW Sec. 16 Twp. 20 Rge. 12 (E)(W) W

County: Barton Total Depth 3499 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. LeRoy Wellbrock was instructed to plug the well as follows:

8 5/8" 222' Cwc.

Sanded hole back to 3400' & dumped 5 sax cement with dump bailer.

Pulled pipe. Run tubing to 435', circulated hole with mud, & displaced

40 sax cement thru tubing. Pulled tubing to 220' & displaced 25 sax

cement. Pulled tubing to 60' & displaced 35 sax cement with Globe

Cementing Company's pump truck, cementing to base of cellar.

Very truly yours,

*Don L. ...*  
Conservation Division Agent