

State of Kansas



FORM - CP-2  
Rev. 9-8-64

15.609.07208.0000

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

OCT 13 1964

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Adminstrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. H. N. Wade of Texaco Inc. has this

date requested permission to plug the following described well:

Mr. Texaco Inc. guarantees payment of the plugging fee.

Operator's full Name: Texaco Inc.

Complete Address: 614 Bitting Bldg., Wichita, Kansas

Lease Name: J. Zecha Well No. # 3

Location: SW SW SE Sec. 12 Twp. 20 Rge. 12 (E) (W) W

County Barton Total Depth 3347 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Ralph Comstock was instructed to plug the well as follows:

8 5/8" 558' Cwc.

Sanded hole back to 3305' & dumped 5 sax cement with

dump bailer. Pulled pipe. Mudded hole to 275'; set rock

bridge; displaced 25 sax cement. Mud to 40'; set rock

bridge; displaced 10 sax cement, cementing to base of cellar.

Very truly yours,

Law Truesdell  
Conservation Division Agent