

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION FORM CP-1
Rev. 2/89
DEC 23 1991
CONSERVATION DIVISION
Wichita

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-009-24,502.0000 (of this well).
(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR L. D. Drilling, Inc. OPERATOR'S LICENSE NO. 6039

ADDRESS R.R. 1 Box 183 B Great Bend, KS. 67530 PHONE # (316) 793-3051

LEASE (FARM) Schartz WELL NO. 6 WELL LOCATION E/2 SW NE COUNTY Barton

SEC. 12 TWP. 20S RGE. 12 (X) or (W) TOTAL DEPTH 3363' PLUG BACK TD _____

Check One:

OIL WELL X GAS WELL _____ D & A X SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 328' CEMENTED WITH 180 SACKS

CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

PERFORATED AT _____

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING _____

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? by operator
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN December 16, 1991 1:00 P. M.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Greg Davidson PHONE # (316) 793-3051

ADDRESS R.R. 1 Box 183 B Great Bend, KS. 67530

PLUGGING CONTRACTOR L. D. Drilling, Inc. LICENSE NO. 6039

ADDRESS R. R. 1 Box 183 B Great Bend, KS. 67530 PHONE # (316) 793-3051

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Greg Davidson
(Operator or Agent)

DATE: December 19, 1991

DEC 23 1991

CONFIDENTIAL

DRILLERS WELL LOG

COMMENCED: 12-10-91
COMPLETED: 12-16-91

L. D. DRILLING, INC.
SCHARTZ #6
E/2 SW NE Sec. 12-20S-12W
Barton County, Kansas

- 0 - 328 Surface
- 328 - 720 Shales & red Bed
- 720 - 1245 Shale
- 1245 - 1930 Shale & Lime
- 1930 - 2680 Lime & Shale
- 2680 - 2855 Lime
- 2855 - 3055 Lime & Shale
- 3055 - 3250 Shale & Lime
- 3250 - 3342 Lime
- 3342 - 3363 Arbuckle
- 3363 R.T.D.

ELEVATION: 1785' GR 1790' KB

FORMATION DATA: (sample)

Anhydrite	559-572	(+1231)
Heebner	2954	(-1164)
Toronto	2971	(-1181)
Douglas	2984	(-1194)
Brown Lime	3077	(-1287)
Lans. KC	3096	(-1306)
Base KC	3316	(-1526)
Arbuckle	3332	(-1542)
RTD	3363	(-1573)

SURFACE CASING:

8 5/8" set @ 328' W/180 sx. 60/40 Pozmix,
2% Gel, 3% CC


A F F I D A V I T

STATE OF KANSAS)
COUNTY OF BARTON)^{SS}

GREG DAVIDSON of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Greg Davidson
Greg Davidson

Subscribed and sworn to before me this 19th day of December, 1991.



Bessie M. DeWerff
Notary Public: Bessie M. DeWerff

My Commission expires: 5-20-93