

15.009.06915.0001

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

RECEIVED FORM CP-1
Rev. 6/4/84
STATE CORPORATION COMMISSION

SEP - 7 1988

CONSERVATION DIVISION
Wichita, Kansas

WELL PLUGGING APPLICATION FORM

(File One Copy)

Drilling Completion

API NUMBER Date 4-17-37 (of this well)

(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Lario Oil & Gas Company OPERATORS LICENSE NO. 5214ADDRESS 301 S. Market, Wichita, KS 67202 PHONE # (316) 265-5611LEASE (FARM) Herman Peter WELL NO. 5 WELL LOCATION SE NE NW COUNTY BartonSEC. 24 TWP. 20S RGE. 11W ~~X~~ 3 11W TOTAL DEPTH 3745' PLUG BACK TO

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL X DOCKET NO. C-554 23,259-CSURFACE CASING SIZE 12-1/2 SET AT 153' CEMENTED WITH 140 SACKS8-1/4 3254' 150 sxsCASING SIZE 5-1/2 SET AT 3409' CEMENTED WITH 200 sxs SACKSPERFORATED AT Open hole 3409' - 3745'CONDITION OF WELL: GOOD POOR CASING LEAK X JUNK IN HOLE XOPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL See back side of this page.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACO-1 FILED? No
No Logs run on this well. (If not, explain)DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Upon approvalPLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

E.G. (Red) KasselmannPHONE # 913) 625-5023ADDRESS P.O. Box 784, Hays, KS 67601PLUGGING CONTRACTOR Halliburton ServicesLICENSE NO. ADDRESS Box 579, Great Bend, KS 67530PHONE # 816) 793-5431

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT

SIGNED: Robert Miller
(Operator or Agent)

Robert Miller, Prod. Supervisor

DATE: 9-6-88

④

Run slick line w/1-1/4" weight to TD 3715' (27' fillup). Check bottom of 3" tubing @ 3405', Bottom of 3" fiberblast tubing 3405'. Pressure 5-1/2" annulus to 76#, pressure immediately equalize w/8-5/8" annulus. Attempted to pull 3" fiberblast tubing, POOH w/3 jts, fishing and wash over to 1678', recovered 80 jts plus one short piece = 1650' of tubing. Attempted to wash over, unable to run wash pipe below 521'. POOH w/ 16-1/2 jts or 522' of 5-1/2" csg. Run 4.75" swg w/2-7/8" tbg to 1650'. This would be the present depth 1650'. Left in hole is 84 jts plus 1 piece or 1755' of 3" fiberblast tubing. Operator suggests following method of plugging this well:

Run tbg to PBTD 1650'. Hook up to tbg and circulate cement to surface, using 65/35 Poz Mix w/10% Gel, 2% econo light and 1/4# flocele per sx. Add hulls to cement if needed for lost circulation material if needed.



Kansas Corporation Commission

MIKE HAYDEN
KEITH R. HENLEY
RICH KOWALEWSKI
MARGALEE WRIGHT
JUDITH McCONNELL
FRANK A. CARO, JR.

GOVERNOR
CHAIRMAN
COMMISSIONER
COMMISSIONER
EXECUTIVE DIRECTOR
GENERAL COUNSEL

CONSERVATION DIVISION
SHARI M. FEIST, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

THIS NOTICE

September 7, 1988

DEC 07 '88

WELL PLUGGING NOTICE

EXPIRES

Herman Peter #5 (SWD)
SE NE NW
Sec. 24-20S-11W
Barton County

Lario Oil & Gas Company
301 S. Market
Wichita, KS 67202


Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,


Shari Feist
Director
State Corporation Commission

DISTRICT #4 2301 E. 13th, Hays, KS 67601 (913) 628-1200