

4
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 15 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Bulldog Pipe & Supply Co.

Complete Address 309 Mayo Bldg., Tulsa, Oklahoma 74103

Lease Name Sessler "A" Well No. 4

Location SW SW SW Sec. 24 Twp. 20 Rge. (E) (W) 11

County Barton Total Depth 3265'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Forbes Casing Pulling

Address Box 221 Great Bend, Kansas License No. 49

Operation Completed: Hour 10A Day 14 Month 8 Year 1969

The above well was plugged as follows:

- Total Depth 3265' 10 3/4 csg set at 198' cwc
- 7" csg set at 325 1/4' cw 150 sk cmt.
- Filled 7" csg W/sd (3235-3265) Dumped 6 sk cmt W/dump bailer. (3200-3235)
- Cutoff and recovered 1610' of 7" csg.
- ~~_____~~
- ~~_____~~
- Set rock bridge (205-190) Dumped 15 sk cmt . (160-190)
- Mud to 140' rock bridge (30-40) Filled to surface with 15 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 8/15/69
INV. NO. 320-U

Signed: Leo J. Massey
Well Plugging Supervisor