



## DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. 85-21LOCATION CSE-SWSEC. 17 TWP. 20 RGE. 11WDry Hole \_\_\_\_\_ Abandoned Oil Well  Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 3 Lease SelleOperator Virginia Drly. Co. Inc. Address 701 Brown Bldg, Wichita Ks.Field \_\_\_\_\_ County BartonTotal Depth 3339 Feet.Plugging Contractor R & S. Pipe Pulling Co.Plugging Contractor's License No. 1.Address Ellinwood Haus.

(Describe briefly the manner in which the well was plugged)

Surface pipe 8 3/4" @ 110' C.W.C. 5 1/2" Oil string set  
3301' w/ 35 ss Cem. Plugged back with Cem.  
to 3281' shot off and pulled 5 1/2" casing.  
Filled hole with mud to 240' set 15' rock  
bridge and dumped 30 ss Cem. mud to 30'  
rock bridge and 10 ss Cem to base of  
cellar

Warren H. Harner  
District Conservation Agent

Date Dec. 27, 1954

12-29-54

