

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 87-26LOCATION NW-NW-NESEC. 17 TWP. 20 RGE. 11WDry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 3 Lease HerterOperator Lohio Petroleum Company Address Box 673, Russell KansField _____ County BartonTotal Depth 3310 Feet.Plugging Contractor West Supply Co, Inc.Plugging Contractor's License No. 14Address Chase Kansas

(Describe briefly the manner in which the well was plugged)

Surface pipe 10 3/4" @ 242' C.W.C. 5 1/2" Oil string
set 3297' w/ 125 sx Cem. Sanded hole to 3280'
and dumped 5 sx Cem. Shot off and pulled
5 1/2" casing. Mudded hole to 240' with 15 sx
fresh fill mud. Set rock bridge and dumped
25 sx Cem. mud to 30' rock bridge and
10 sx Cem. to base of cellar

1-20-55

Warren H. Horner
District Conservation Agent

Date Jan 15, 1955

PLUGGING
FILE SEC 17 T 20 R 11W
BOOK PAGE 87 LINE 26

FILED
STATE COM

JAN 20 1955

CONSERVATION DIVISION
Wichita, Kansas