

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 48-25

LOCATION SW-NE-SE

SEC. 17 TWP. 20 RGE. 11w

Dry Hole          Abandoned Oil Well   L   Abandoned Gas Well         

I have this date completed supervision of plugging of:

Well No. 2 Lease Hertter "B"

Operator Virginia Drilg. Co Address 701 Brown Bldg. Wichita, Ks.

Field          County Barton

Total Depth 3325 Feet.

Plugging Contractor R & S. Pipe pulling Co.

Plugging Contractor's License No. 1.

Address Box 192, Ellinwood Kans.

(Describe briefly the manner in which the well was plugged)

Surface pipe 8 5/8" @ 110' c.w.c. 5 1/2" @ 3300'  
w/ 125 st cem. L.W.P. 3200' top Ref. 3166'  
Sanded hole to 3150' and dumped 5 st Cem.  
Shot off and pulled 5 1/2" casing. Pumped 20 st  
fresh jell mud, Plug and 80 st Cem. Filling  
hole and surface casing from approx 240' to  
base of cellar with cem.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 21 1954

CONSERVATION DIVISION  
Wichita, Kansas

7-21-54

Warren H. Horner  
District Conservation Agent

Date July 18, 1954

**PLUGGING**  
FILE SEC 17 TWP 20 R 11W  
BOOK PAGE 48 LINE 25