

KANSAS

4
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
MAR 22 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name D. R. Lauck Oil Company, Inc.

Complete Address: 301 S. Broadway, Wichita, Kansas 67202

Lease Name Hagen Well No. # 1

Location C W/2 NE NE Sec. 21 Twp. 20 Rge. 11 (E) (W) W

County Barton Total Depth 3370

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Glenn & Smith Pipe Pulling Company

Address: 204 E. 6th., Ellinwood, Kansas License No. # 396

Operation Completed: Hour 1:15PM Day 18 Month 3 Year 1968

The Above well was plugged as follows:

8 5/8" 210' Cwc.

Sanded hole back to 3290' & dumped 5 sax cement with dump bailer. Pulled pipe.

Set plug @ 215' & displaced 5 sax cement. Let set over night. Bailed hole dry &

displaced 25 sax cement. Mud to 40', set rock bridge, & displaced 10 sax cement,

cementing to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Don Truman
Well Plugging Supervisor

INVOICED
DATE 3/22/68
INV. NO. 7460-W