

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Barton County. Sec. 22 Twp. 20S Rge. 11W (E) (W)

Location as "NE/CNW/SW" or footage from lines NE NE SE

Lease Owner W. L. Hartman

Lease Name Dannebohm Well No. 4

Office Address P. O. Box 54, Wichita, Kansas 67201

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed June 6, 1952

Application for plugging filed September 8, 1965

Application for plugging approved September 9, 1965


Plugging commenced September 13, 1965

Plugging completed September 16, 1965

Reason for abandonment of well or producing formation Considered no longer commercial

If a producing well is abandoned, date of last production August 1, 1965

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Donald Truan

Producing formation Arbuckle Depth to top 3302 Bottom 3312 Total Depth of Well 3312 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	123'	
				5-1/2"	3304'	2858'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

- 3200' to 3160' Sand bridge
- 3160' to 3130' 5 sacks cement
- 3130' to 200' Mud
- 200' to 100' 30 sacks cement
- 100' to 30' Mud
- 30' to cellar 10 sacks cement

RECEIVED  
STATE CORPORATION COMMISSION

SEP 22 1965

CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor Glenn & Smith Pipe Pulling Co.  
Address P. O. Box 156, Ellinwood, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.  
W. L. Hartman, owner (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. L. Hartman

P. O. Box 54, Wichita, Kansas 67201

(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of September, 19 65

Berenice Kooker  
Berenice Kooker, Notary Public.

My commission expires January 12, 1968



## CERTIFIED DRILLER'S LOG

Company: W. L. Hartman Lease: Dannebohm #4  
 Contractor: H & H Drilling Company Location: NE NE SE, 22-20-11W  
 Barton County, Kansas  
 Commenced: 5-14-52  
 Completed: 5-27-52 (Rotary) Casing Record:  
 123' 8-5/8" cem. w/80 sax.  
 3304' 5-1/2" cem. w/100 sax.  
 Elevation: 1760 D. F.


FORMATION	DEPTH	REMARKS
Shale	105-498	
Anhydrite	498-512	
Shale & Shells	512-1084	
Shale Salt	1084-1410	
Shaly Shells	1410-1545	
Lime & Shale	1545-1651	
Lime	1651-1881	
Shale & Lime	1881-2027	
Shale	2027-2535	
Lime	2535-2587	
Lime & Sand	2587-2650	
Lime	2650-3304	
Rotary Total Depth	3304	

RECEIVED  
STATE CORPORATION COMMISSION

SEP 9 1965

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that this is a true and correct copy of the above log, to the best of my knowledge.

  
R. E. Hartman

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK)

Subscribed and Sworn to before me this 31st day of May 1952.

  
Notary Public

My Commission Expires: Jan. 1, 1956