

15.009.14633.0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 18 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name F. G. Holl

Complete Address 6427 E. Kellogg Wichita, Kansas 67207

Lease Name Kasselman Well No. 3

Location SE SW SW Sec. 22 Twp. 20 Rge. (E) (W) 11

County Barton Total Depth 3386

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Pipe Pullers, Inc.

Address Box 486 Ellinwood, Kansas 67526 License No. 462

Operation Completed: Hour 10 A Day 16 Month 7 Year 1973

The above well was plugged as follows:

Total Depth 3386' 8 5/8 csg set at 252' cwc 275 sk.

5 1/2 csg set at 3165' W/75 sk. FBTD: 3090' with top perf. (3080')

Set 5 1/2 wood plug at 3050' -poured 10' sand -dumped 5 sk cmt W/dump bailer.

Cutoff and recovered 2018' of 5 1/2 csg.

Pumped down: 8 5/8 csg with 20 sk gel & water W/300 lbs hulls, -released 8 5/8 plug

and pumped 100 sk cmt.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo Fitzmaurice
Well Plugging Supervisor

INVOICED

DATE 7/18/73

INV. NO. 7647-W