

KANSAS

Form CP-3

Rev. 6-4-68

STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT DEC 27 1976 12-27-76

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

CONSERVATION DIVISION
Wichita, Kansas

API Number 15 - 009-14694.0000 (of this well)

Operator's Full Name Lario Oil & Gas Co.
Complete Address 301 South Market, Wichita, KS 67202
Lease Name Peter Well No. 6
Location SWNW NW Sec. 24 Twp. 20 Rge. 11 (W) X
County Barton Total Depth 3270
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Kelso Casing Pulling
Address Box 176 Chase, Ks. 67524 License No. 683
Operation Completed: Hour 11 ^{AM} Day 23 Month 12 Year 1976

The above well was plugged as follows:

Sanded to 3240' & 6" x Cement @ Dump Bailer
Shot 7" casing @ 1765' & spotted 25" x Cement
Pulled 5 jts of 7" casing & circ Gel @ 25" x Mud Gel
@ 1600' - Pulled 7" casing to 490' & Pumped in 180
5" x Cement Pulled 5 jts 7" casing & Pumped in 75" x Cement. Ran
2" tubing in hole to 60' & Circ Cement @ 125" x Cement
Cable tool Hole No surface casing. -
3240' of 7" casing cemented @ 50" x Cement. -

I hereby certify that the above well was plugged as herein stated.

Signed: Dwain Rankin
Well Plugging Supervisor

INVOICED

DATE 12-29-76

INV. NO. 4392-W