

15.009.14712.0000

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION

MAY 20 1974 5-20-74

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Mobil Oil Corporation

Complete Address P. O. Box 1934, Oklahoma City, Oklahoma 73101

Lease Name H. J. Roetzel "B" Well No. # 17

Location NW SE SE Sec. 24 Twp. 20 Rge. 11 (E) (W) W

County Barton Total Depth 3261

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Glenn's Pipe Pulling Corporation

Address Box 156, Ellinwood, Kansas License No. # 686

Operation Completed: Hour 10:00 A.M. Day 16 Month 5 Year 1974

The above well was plugged as follows:

13" csg. 198' Cwc. Perf. 3050'

Sanded hole back to 3000' & dumped 5 sax cement with dump bailer. Pulled pipe.

Squeezed well with 25 sax mud, 1 sax hulls, & 150 sax cement with Allied Cementing

Company's pump truck, cementing from 320' to base of cellar.

INVOICED I hereby certify that the above well was plugged as herein stated.

DATE 5/21/74

INV. NO. 9145-W

Signed: Lawrence  
Well Plugging Supervisor