

15.009.14688.0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 8 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Bulldog Pipe & Supply Co.
Complete Address 309 Mayo Bldg., Tulsa, Oklahoma 74103
Lease Name Sessler "A" Well No. 52
Location NW SW SW SW Sec. 24 Twp. 20 Rge. (E) (W) 11
County Barton Total Depth 3269
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Forbes Csg Plg., Inc.
Address Box 221 Great Bend, Kansas License No. 49
Operation Completed: Hour 11A Day 6 Month 8 Year 1969

The above well was plugged as follows:

Total Depth 3269' 10 3/4 csg set at 196' cwc
7" csg set at 3255' cw 150 sk cmt.
Filled 7" csg W/sd (3240-3269) Dumped 7 sk cmt W/dump bailer. (3200-3240)
Recovered 1600' of 7" csg.
Mud to 190' Set rock bridge (180-190) dumped 8 sk cmt with dump bailer. (140-180)
Dumped 4 yds readymix cmt. (0-140)

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/8/69
INV. NO. 258-W

Signed: Leo J. Murray
Well Plugging Supervisor