

15.009.04957.0000

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
1-14-74 JAN 14 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name National Cooperative Refinery Association

Complete Address P. O. Box # 6, Great Bend, Kansas 67530

Lease Name Brown Well No. # 5

Location SW NE SE Sec. 28 Twp. 20 Rge. 12 (E) (W) W

County Barton Total Depth ~~3541~~ 3476'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Southwest Casing Pulling Company

Address Box 364, Great Bend, Kansas License No. # 399

Operation Completed: Hour 3:30 P.M. Day 10 Month 1 Year 1974

The above well was plugged as follows:

8 5/8" csg. 290' Cwc. Perf. 3410'  
Sanded hole back to 3400' & dumped 5 sax cement with dump bailer. Pulled pipe.  
Squeezed well with 2 sax hulls, 20 sax mud, released plug, & displaced 100 sax  
cement with Allied Cementing Company's pump truck, cementing from 320' to base  
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Don [Signature]  
Well Plugging Supervisor

DATE 1/14/74

INV. NO. 8403-W