

15.009.00783.0060

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
MAY 6 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Petroleum, Inc.

Complete Address R. R. # 2, Great Bend, Kansas 67530

Lease Name Hulme "D" Well No. # 1

Location SE NW NW Sec. 16 Twp. 20 Rge. 12 (E) (W) W

County Barton Total Depth 3499

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Forbes Casing Pulling Company

Address Box 221, Great Bend, Kansas License No. # 637

Operation Completed: Hour 1 P.M. Day 4 Month 5 Year 1971

The above well was plugged as follows:

8 5/8" 222' Cwc.
Sanded hole back to 3400' & dumped 5 sax cement with dump bailer. Pulled pipe.
Run tubing to 435', circulated hole with mud, & displaced 40 sax cement thru
tubing. Pulled tubing to 220' & displaced 25 sax cement. Pulled tubing to 60'
& displaced 35 sax cement with Globe Cementing Company's pump truck, cementing
to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Don Duward
Well Plugging Supervisor

DATE 5/13/71

INV. NO. 3684-W