



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
AUG 9 1971
CONSERVATION DIVISION
Wichita, Kansas
8-9-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Johnnie Crowe of Garvey Drilling Company has this date requested permission to plug the following described well:

Mr. Petroleum, Inc. guarantees payment of the plugging fee.

Operator's full Name: Petroleum, Inc.

Complete Address: 300 West Douglas, Wichita, Kansas 67202

Lease Name: Hulme "D" Well No. # 3

Location: N/2 SW NW Sec. 16 Twp. 20 Rge. 12 (E)(W) W

County: Barton Total Depth 3450 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Johnnie Crowe was instructed to plug the well as follows:

8 5/8" 218' Cwc,

Circulated hole with heavy mud to 480', set plug, & displaced 40 sax

cement thru drill pipe, Mud to 210' & displaced 25 sax cement thru

drill pipe. Mud to 40', 1/2 sax hulls, plug, & displaced 10 sax

cement with Globe Cementing Company's pump truck, cementing to base

of cellar.

Very truly yours,

Don L. Lewis
Conservation Division Agent