

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Barton SEC. 28 TWP. 20S RGE. 12W E/W
Location as in quarters or footage from lines:
SE SW NE

Locate Well
correctly on above
Section Platt.

Lease Owner Southern States Oil Company
Lease Name Spacil #9 Well No. _____
Office Address P.O. Box 1365 Great Bend, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 10-22-82
Plugging completed 10-27-82
Reason for abandonment of well or producing formation Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Scheck
Producing formation _____ Depth to top _____ bottom _____ T.D. 3443'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	278'	none
				5-1/2"	3436'	2010'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged off bottom with 5 sacks cement, sand to 3400' and 5 more sacks cement.
Shot casing @803', 2628', 2430', 2227', 2025', pulled a total of 61 joints of
5-1/2" casing. Plugged well with 25 sacks cement, 4 sacks hulls, 12 sacks gel,
70 sacks cement, 3 sacks gel, 1 sack hulls, 8-5/8" plug and 70 sacks cement,
50/50 pos, 4% gel, 3% cc.
Plugging Complete.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347 Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of October, 19 82

My Commission expires:



Irene Hoover
Notary Public.
STATE CORPORATION COMMISSION

NOV 1 1982

CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
STATE COORDINATION COMMISSION
OCT 08 1982
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG

PINE OIL & ROYALTY CO., INC.

Commenced: January 28, 1959

Contractor: Quaker Drilling Co., Inc.

Completed: February 5, 1959

Special No. 9

Elevation: 1848 KB

SE SW NE Section 28-20S-12W
Barton County, Kansas

Casing Records:

Set 8 5/8 inch casing at 278 feet with 250 sacks cement

Set 5 1/2 inch casing at 3436 feet with 125 sacks cement

(Figures Indicate the Bottom of the Formations)

<u>FORMATION</u>	<u>DEPTH</u>	<u>FORMATION TOPS</u>	
Surface Soil and Sand	215	Heebner	3036 -1188
Shale	280	Brown Lime	3159 -1311
Shale and Shells	300	Lansing	3175 -1327
Red Bed	630	Base of Kansas City	3393 -1545
Anhydrite	655	Conglomerate	3408 -1560
Shale and Shells	1545	Arbuckle	3425 -1577
Sandy Lime and Shale	1810	Rotary Total Depth	3443 -1595
Lime	1970		
Lime and Shale	2270		
Shale	2555		
Lime and Shale	3275		
Lime	3327		
Lime and Shale	3443		

We hereby certify the foregoing to be a true and correct copy of the Driller's Log of the well drilled in the SE SW NE of Section 28, Township 20 South, Range 12 West, Barton County, Kansas.

QUAKER DRILLING CO., INC.

By:


 Thomas M. McCaul

SUBSCRIBED AND SWORN TO before me a Notary Public this 26th day of March, 1959.

Virginia Mandell, Notary Public

MY COMMISSION EXPIRES:
August 10, 1961