

STATE OF KANSAS
STATE CORPORATION COMMISSION
J. S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-009-19038-00-02

RECEIVED
10-9-02
OCT 09 2002

KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE NAME Spacil

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 28 TWP. 20S RGE. 12W (E) or (W)

COUNTY Barton

LEASE OPERATOR ZENITH DRILLING CORPORATION

ADDRESS P.O. Box 780428 Wichita, Kansas 67278-0428

PHONE (316) 684-9777 OPERATORS LICENSE NO. 5141

Date Well Completed

Character of Well SWD

Plugging Commenced 9-26-02

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10-01-02

This plugging proposal was approved on (date)

Patrick Staab (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3560'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	260'	None
				5-1/2"	3560'	None
				3"	3483'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from feet to feet each side. Pumped bottom with 50 sacks of 60/40 pos, 10% gel, 2% cc. Shot pipe @2400', shot @1400', perforated @1475', hooked onto 3" tubing and pumped 355 sacks cement and had return up 8-5/8". Pumped 85 sacks cement and circulated up 8-5/8", shot pipe @350', pumped 35 sacks cement and circulated up 5-1/2" casing. 60/40 pos. 10% gel.

Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Zenith Drilling Corporation

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 7th day of October, 2002

[Signature]
Notary Public

My Commission Expires:



OK