


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Barton County, Sec. 16 Twp. 20 Rge. (E) 12 (W)  
Location as "NE/CNW/SW" or footage from lines NW SW NE  
Lease Owner Chas. Hulme Drilling Contractor  
Lease Name J. H. Hulme Well No. 1  
Office Address P.O. Box 36, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed June 6 19 57  
Application for plugging filed verbal application June 6 19 57  
Application for plugging approved June 6 19 57  
Plugging commenced June 6 19 57  
Plugging completed June 6 19 57  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? \_\_\_\_\_

Name of Conservation Agent who supervised plugging of this well Mr. R.M. Brundage  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		281'		8 5/8"	surface	casing

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Hole filled with heavy mud to 240 feet; 1/3 sack of cotton seed hulls and Halliburton plug pushed to 240 feet with drill pipe; 20 sacks cement mixed, poured through drill pipe to 195 feet; filled hole with heavy mud to 20 feet; 1/3 sack of cotton seed hulls and Halliburton plug pushed to 20 feet; .7 sacks cement to 5 feet below surface

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Chas. Hulme Drilling Contractor  
Address P.O. Box 36, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
C. E. Byars (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. E. Byars  
P.O. Box 36, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 10 day of June, 19 57

My commission expires October 15, 1957

**RECEIVED**  
STATE CORPORATION COMMISSION  
Notary Public.

PLUGGING  
SEC 16 T. 20 R. 12W  
BOOK PAGE 18 LINE 26

JUN 11 1957  
CONSERVATION DIVISION  
Wichita, Kansas

W E L L L O G

Company - Chas. Hulme Drlg. Contr.

Sec. 16-20S-12W

Farm - J.H. Hulme Well No. 1

Loc. NW SW NE

Total Depth - 3457 Ft.

Comm. - May 2, 1957 Comp. June 6, 1957

Elevation - 1830' D.F.  
D & A.

Contractor - Chas. Hulme Drlg. Contr.

Casing - 8 5/8" @ 281' w/250 sacks Posmix 2% c.c.

0	281	Clay & Sand
281	645	Red Bed
645	680	Anhydrite
680	1450	Shale & Shells
1450	2130	Lime
2130	2905	Lime & Shale
2905	3015	Lime
3015	3205	Lime & Shale
3205	3410	Lime
3410	3427	Lime & Conglomerate
3427	3437	Cherty Lime
3447	3457	Arbuckle Lime
3457		R.T.D.

State of Kansas )  
 )  
 County of Barton)

ss:

I, C. E. Byars, of Chas. Hulme Drilling Company, upon oath state that the above and foregoing is a true and correct copy of the log of the J.H. Hulme #1 well.

*C. E. Byars*  
 C. E. Byars

Subscribed and sworn to before me this 10th day of June, 1957

*Fred Williams*  
 Notary Public

My Commission Expires: October 15, 1957

PLUGGING			
FILE	SEC. 16	T. 20	R. 12W
BOOK	PAGE 18	LINE	26

**RECEIVED**  
 STATE CORPORATION COMMISSION

JUN 11 1957

CONSERVATION DIVISION  
 Wichita, Kansas