

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER None

LEASE NAME Opal Lanterman

WELL NUMBER 4

SPOT LOCATION 990' FSL & 990'

SEC. 16 TWP. 20 RGE. 12 (NW) or (W)

COUNTY Barton

Date Well Completed 4-16-57

Plugging Commenced 4-24-84

Plugging Completed 4-24-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Getty Oil Company

ADDRESS 2705 Vine, Unit #4, Hays, Kansas 67601

PHONE # (913) 628-1039 OPERATORS LICENSE NO. 6237

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dist. #6

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation Arbuckle Depth to top 3438' bottom 3451' T.D. 3451'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Arbuckle	Oil	3438'	3451'	8-5/8"	656	None
				5 1/2"	3457	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Pumped 50 sks 50/50 Poz w/ 8% gel & 3% CaCl2 down 5 1/2" csg @ 4 BPM & 1750 psi. Closed in 5 1/2" csg @ 1500 psi. Pumped down 5 1/2" & 8-5/8" csg annulus w/ 200 sks 50/50 Poz, 8% gel & 3% CaCl2 @ 1/2 BPM @ 450 psi. Closed well in. Plugging witnessed by KCC rep. Gilbert Scheck. Cut csg off below plow depth, welded steel plate & cleaned location.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. 5287
Address Box 579, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Ellis, ss.


Frank Renard (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Frank Renard

(Address) 2705 Vine, Unit #4, Hays, KS 67601

RECEIVED
STATE CORPORATION COMMISSION

MAY 03 1984
5-3-84
CONSERVATION DIVISION
My Commission Expires: _____



Subscribed and sworn to before me this 2nd day of May, 19 84
Bobbie Schippers
Notary Public