

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado, Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15.009.21429.0000

API NUMBER 15-009-20,611

LEASE NAME Buckbee

WELL NUMBER 3

         Ft. from S Section Line

         Ft. from E Section Line

SEC. 12 TWP. 20S RGE. 12W (E or W)

COUNTY Barton

Date Well Completed         

Plugging Commenced 1-17-92

Plugging Completed 1-23-92

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Milton Lackey

ADDRESS RR #2 Inman, Ks. 67546

PHONE#(316) 585-2119 OPERATORS LICENSE NO. 9132

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on          (date)

by          (KCC District Agent's Name).

Is ACO-1 filed?          If not, Is well log attached?         

Producing Formation          Depth to Top          Bottom          T.D. 3600'

Show depth and thickness of all water, oil and gas formations.

RECEIVED  
KANSAS CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	307'	none
				4 1/2"	3395'	955'

1-27-92  
JAN 27 1992

CONSERVATION DIVISION  
WICHITA, KS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from          feet to          feet each set.  
Sanded bottom to 3342' ran 4 sacks cement. Shot pipe @2222', 2110', 2000', 1919', 1841'. Went down 4 1/2" circulated cement from 1000' to surface pulled 4 1/2" out used 250 sacks cement. Went down 8 5/8" casing mixed 50 sacks, Max Pressure 400#, Shut In @200#, 300 sacks.  
(If additional description is necessary, use BACK of this form.) 60/40 8% gel.

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Milton Lackey

STATE OF Kansas COUNTY OF Rice, ss.


R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 24 day of January, 19 92

My Commission Expires:         



Notary Public

*Hubert*  
*Milton*  
#9123

*Wants*

15.009.21629.0000

ORDER NO. 1215

DATE COMMENCED: May 29, 1977  
DATE COMPLETED: June 5, 1977

ICOR ADDIS  
DUCKER # 9  
C 2/2 5 1/4  
Sec. 12, T20S, R12W  
Barton County, Ks.

- 0 - 286' Shale & Sand
- 286 - 557' Red Bed & Shale
- 557 - 576' Anhydrite
- 576 - 2694' Shale & Lime
- 2694 - 2961' Lime
- 2961 - 2966' Shale
- 2966 - 2975' Lime & Shale
- 2975 - 2992' Lime
- 2992 - 3085' Shale
- 3085 - 3102' Lime & Shale
- 3102 - 3324' Lime
- 3324 - 3344' Lime, Shale
- 3344 - 3600' Dolomite
- 3600' RTD

ELEVATION: 1795 KB

FORMATION DATA

Anhydrite	557
Topoka	2674
Hoobnor	2961
Foranto	2975
Douglas	2992
Jr. Lime	3085
Kansas City	3102
Base K.G.	3324
Conglomerate	3338
Arbuckle	3344
RTD	3600

AIRFACE PIPE: Set  
used 32 #, 8 5/8"  
pipe @ 307' w/225  
sacks 50/50 Pozmix  
2 % gel, 3 % co.

INDUCTION PIPE: Set  
at 3395' w/125 sacks  
50/50 Pozmix, w/10 %  
salt

A P P E A R A N C E

State of Kansas  
County of Barton ) ss.

Leonard Williamson, of lawful age does swear and state that the facts and  
statements herein contained are true and correct to the best of his knowledge.

*Leonard Williamson*

Subscribed and sworn to before me this \_\_\_\_\_ day of June 1977

*Martha McHague*  
Notary Public

My Comm. Expires: April 11, 1982