


STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
WICHITA, KANSAS 67217

FORM CP-4

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plot

Barton County. Sec. 24 Twp. 20 Rge. 11W (E) (W)
Location as "NE/CNW/SE/SW" or footage from lines. C NE NE SW
Lease Owner Gulf Oil Corporation
Lease Name Charles Sessler #1 Well No. _____
Office Address Oklahoma City, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 9/2/75 9/2/75 _____ 19____
Plugging completed 9/4/75 _____ 19____
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Rankin
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3253 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED STATE CORPORATION COMMISSION SEP 08 1975 CONSERVATION DIVISION Wichita, Kansas	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4	166	none
				6	3241	1195'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole, hit top of tubing at 1220', shot cement out of cellar.
Had welder strap collar, shot pipe at 1210', pulled 39 joints.
Plugged well with 100 lbs. of hulls, 25 sacks gel and 150 sacks
50-50 pos, 6% gel.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso

CHASE, KANSAS
(Address)

Subscribed and Sworn to before me this 5th day of September, 19 75

My commission expires _____



Margaret Melcher
Notary Public.

WELL NO. 1 LEASE Charles Sessler COMPANY Gulf Oil Corporation A.F.E. 2265

DATE—DRILLING BEGAN 5-12-37 WELL COMPLETED 6-15-37 FIRST PRODUCTION 6-2-37

SAND RECORD Siliceous lime, 3243' - 3255' TOTAL DEPTH 3253'

INITIAL PRODUCTION "P" 2,225 oil, no water. (6/17)

CASING RECORD

SIZE	WEIGHT	THD.	CLASS	MAKE	SET AT DEPTH	SACKS CEMENT	LBS. CAL. CHLO.	PULLED	LEFT IN
10-3/4"	32	3	New	SC LW	166'	160	400	-	166'
6"	15	10	New	Seamless	3241'	140	-	-	3241'

(*) "F," FLOWING NATURALLY; "L," AIR GAS LIFT; "S," SWABBING; "P," PUMPING.

S— 24 T— 20S R—11W

ELEVATION— 1751'

ACIDIZED: 6-14-37 with 4,000 gallons of acid solution.

RECEIVED
STATE CORPORATION COMMISSION

JUL 18 1975

CONSERVATION DIVISION
Wichita, Kansas

Sand	0 to 65'
Shale & red bed	145
Red bed & shells	170
Red bed, shale & shells	392
Red bed & shells	440
Shale & shells	730
Lime & shale	870
Shale & lime shells	1080
Salt	1250
Salt & shells	1265
Shale & shells	1297
Lime	1430
Broken lime	1555
Lime	1620
Sand & lime	1655
Lime - broken	1750
Lime	1915
Lime - broken	2125
Lime & shale	2294
Broken lime	2488
Lime	2531
Broken lime	2590
Lime	2752
Shale	2775
Lime	2853
Lime - broken	2925
Shale & shells	2967
Broken lime	2985
Lime	3255 TD

RECEIVED
STATE CORPORATION COMMISSION

JUL 18 1975

CONSERVATION DIVISION
Wichita, Kansas