

GP

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Barton County, Sec. 21 Twp. 20 Rge. 11 (E) (W)

Location as "NE/CNW%SW%" or footage from lines SW SW SW

Lease Owner Bulldog Pipe & Supply Company

Lease Name Sessler Well No. A-4

Office Address 309 Mayo Building Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed _____ 19__

Application for plugging filed 7-23-69 19__

Application for plugging approved 7-24-69 19__


Plugging commenced 8-11-69 19__

Plugging completed 8-14-69 19__

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Donald Truan

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3265 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4	198	None
				7	None	1620

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Moved in. Cleaned out cellar. Sanded to 3235'. Dumped 6 sacks of cement. Working pipe.

Working pipe. Shot pipe at 2000' - 1800' and 1610'. Pulling pipe.

Pushed plug to 205'. Set 15' rock bridge. Dumped 15 sacks of cement.

Mudded to 40' rock bridge. Capped well with 15 sacks of cement.

8-19-1969

RECEIVED
STATE CORPORATION COMMISSION
AUG 19 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling Company, Inc.

Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

James W. Rockhold

(employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) _____

James W. Rockhold

P. O. Box 221 Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 15 day of August, 19 69

(Signature)

My commission expires May 27, 1973

Notary Public.

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.

412 Union National Bank Bldg, Wichita, Kansas.


COPY

IND. TERR. ILL. OIL CO.
Rosa Sessler No. 4

SEC. 24 T. 20 R. 11W.
SW SW
330' fr S.L. 330' fr W.L.

County Barton.

Total Depth. 3265
Comm. 10-11-37 Comp. 11-1-37
Shot or Treated.
Contractor. Schoonfold-Hunter-Kitch.
Issued. 1-1-38



CASING.

Rotary and Cable.

103/4" 198'
7" 3254'

Elevation.

Production. Pot. 644 B.

Figures Indicate Bottom of Formations.

sand	70
shale	130
shale and shells	215
red bed and shells	445
red bed shale and shells	745
shell and shale	985
shale and salt	1240
shale shells and salt	1380
lime shells and shale	1490
shale and shells	1650
sand hard	1750
shale	1886
shale and salt	2010
shale and lime	2271
shale	2495
lime	2510
shale and lime	2615
lime hard	2675
lime	3255
lime brown soft	3265
lime grey hard	3268
3268 equals 3265	Corr. by Steel line Meas.
Total Depth.	3265

RECEIVED
STATE CORPORATION COMMISSION
JUL 24 1938
CONSERVATION DIVISION
WICHITA, KANSAS