

STATE OF KANSAS
STATE CORPORATION COMMISSION

File All-States Oil Company
State Department of
State of Kansas
Conservation Commission
State Corporation Commission

P. O. Box 17027
Wichita, Kansas 67217

Locate well correctly on above
Section Plot

WELL PLUGGING RECORD

Barton County, Sec. 17 Twp. 20 Rge. 11 (E) (W)
Location at "NE/CNW/SE/SW" or footage from line S/2 NW/4
Lease Owner Westtrans Oil Co.
Lease Name Clawson #3 Well No. _____
Office Address Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 9/11/74 _____ 19____
Plugging completed 9/21/74 _____ 19____
Reason for abandonment of well or producing formation depleted.
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3319 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	284	none
				5 1/2	3287' ~~678'~~	678'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole, bridge at 700', rigged up on 5 1/2" casing. Couldn't knock bridge out, shot pipe at 681', pulled 21 joints of 5 1/2" casing. Allied pumped 20 sacks mud and 100 sacks cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

OCT 15 1974

CONSERVATION DIVISION
Wichita, Kansas 10-15-1974

Name of Plugging Contractor _____
Address _____
(If additional description is necessary, use BACK of this sheet)
KNIGHT CASING PULLING CO., INC.
CHASE, KANSAS


STATE OF KANSAS COUNTY OF RICE
NOEL J. KNIGHT _____ ss.

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) _____

CHASE, KANSAS


Subscribed and Sworn to before me this 23rd day of September 1974



Notary Public.

VIRGINIA DRILLING CO. INC. ET AL.
Clawson No. 3SEC. 17 T. 20 R. 11W
CNE SE NWTotal Depth. 3319
Comm. 1-6-41 : Comp. 1-27-41
Shot or Treated. 5000 gal acid.
Contractor. Virginia Drilg. Co. Inc.
Issued. 6-21-41

County Barton.



CASING.

8 3/8" 284'
5 1/2" 3287'

Elevation.

Production. Pot. 288 B.

Figures Indicate Bottom of Formations.

sand and shale	150
shale and shells	190
sand and shale	240
shale	205
red rock	235
reamed to 205	
red bed	469
red rock	530
anhydrite	555
shale and shells	646
shale	940
shale and shells	1070
salt and shale	1295
shale and shells	1390
lime	1637
shale and lime	1725
sdv shale & lime	1794
sdv lime	1805
shale and lime	1845
shale	1912
shale and B. lime	1935
lime and shale	2034
shale	2041
scale and lime	2396
shale	2460
lime	2491
B. lime & shale	2552
lime	2606
shale	2652
lime and shale	2669
lime	2832
lime and shale	3040
shale	3085
lime and shale	3290
lime Arbuckle	3319

Total Depth.

Top of Arbuckle 3284

RECEIVED
STATE CORPORATION COMMISSION
SEP 13 1944
CONSERVATION DIVISION
Wichita, Kansas