



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Morton Specter of Specter Pipe & Supply, Inc. has this date requested permission to plug the following described well:

Mr. Morten Soecter guarantees payment of the plugging fee.

Operator's full Name: Specter Pipe & Supply, Inc.

Complete Address: Box 661, Russell, Kansas 67665

Lease Name: Peters Well No. # 1

Location: C NL S/2 NW Sec.24 Twp. 20 Rge. 11 (E)(W) W

County: Barton Total Depth 3258 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Ralph Lynch was instructed to plug the well as follows:

12 1/2" 218' Cwc.

Sanded hole back to 3250' & dumped 5 sax cement with dump bailer.

Circulated hole with mud @ 500' & displaced 35 sax cement thru pipe

@ 400'. Displaced 35 sax cement thru pipe @ 200'. Pulled remaining

pipe, set rock bridge @ 35', & displaced 15 sax cement with pump

truck, cementing to base of cellar. Very truly yours

RECEIVED
STATE CORPORATION COMMISSION

SEP 26 1969

9-26-1969

J. Lewis Brock
Wichita, Kansas
Conservation Division Agent