


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Barton County. Sec. 19 Twp. 20S Rge. (E)11 (W)  
Location as "NE/CNW/SW" or footage from lines NE NW NE  
Lease Owner Raymond Oil Company, Inc.  
Lease Name Scheufler Well No. 2  
Office Address 410 Fourth National Bank Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed Unknown 19\_\_  
Application for plugging filed December 9 1964  
Application for plugging approved December 10 1964  
Plugging commenced Dec 23 1964  
Plugging completed Dec 28 1964  
Reason for abandonment of well or producing formation No longer commercially productive

If a producing well is abandoned, date of last production December 11 1964  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? es

Name of Conservation Agent who supervised plugging of this well Don Tuin  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3324 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8"	240'	
				5"	3307'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

*Filled back with gravel to 3100'. Dumped 5 sacks of cement. Shot pipe off at 2696'. Pulled pipe and squeezed 15 sacs of Jet Mud and 80 sacks of cement with Halliburton.*

RECEIVED  
STATE CORPORATION COMMISSION

DEC 31 1964  
12-31-1964

CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor Bert Self (If additional description is necessary, use BACK of this sheet)  
Address Hutchinson, Kans.


STATE OF Kans. COUNTY OF Reno, ss.  
Employee (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bert Self  
R. R. #4, Hutchinson, Kans.  
(Address)

SUBSCRIBED AND SWORN to before me this 29th day of Dec, 1964

My commission expires October 15, 1965

Dorothy Self  
Notary Public.



Date Commenced: February 15, 1942.  
Date Completed: March 6, 1942.

Pipe Record

Contractor: Hollow Drilling Company, Inc.  
Inman, Knasas.

Ran 9 jts. SH 8 $\frac{1}{4}$ " pipe, cemented at  
235' with 85 sx Regular and 25 sx  
Quickset.

Tools: Rotary drilling tools,  
completed with cable.

Ran 101 jts. 5 $\frac{1}{2}$ " OD CRnd th d pipe at  
3305; cemented with 100 sx Regular.

LOG

0	10	Cellar
10	145	Sand
145	190	Shale and shells
190	215	Sand
215	236	Shale and shells
236	510	Shale
510	540	Anhydrate lime
540	720	Shale
720	1050	Shale and shells
1050	1327	Salt
1327	1475	Shale and lime shells
1475	1580	Lime
1580	1605	Lime and shale
1605	1625	Sand
1625	1775	Shale and shells
1775	1830	Lime
1830	1870	Shale and shells
1870	2000	Shale and lime shells
2000	2045	Shale and shells
2045	2080	Lime
2080	2200	Shale and lime shells
2200	2350	Lime and shale
2350	2450	Shale and lime shell
2450	2520	Shale and lime
2520	2645	Shale and lime shells
2645	2670	Shale and lime
2670	2715	Topeka lime
2715	2890	Lime
2890	2940	Shale
2940	2998	Lime
2998	3075	Shale
3075	3308	Lime
	3306	Top of Arbuckle Lime
3306	3304	Top of Arbuckle Derrick Floor Correction
3304	3324	Arbuckle Lime
3324		T.D.

Potential Test 3-6-1942,  
50 bbls. Temporary swab. test.

Remarks

Cored from 3306 to 3311'.  
Treated well with 4000 gallons acid.  
Hole filled 300" oil in 10 $\frac{1}{2}$  hrs.

RECEIVED  
STATE CORPORATION COMMISSION

JAN 6 1955

CONSERVATION DIVISION  
Wichita, Kansas

15.009.14606.0000

This is the only Driller's Log available on  
the #2 Scheufler.

There is nothing in file on the #1 Scheufler.  
We purchased these wells for salvage only.

*Raymond O'Neil*

**RECEIVED**  
STATE CORPORATION COMMISSION

JAN 6 1965

**CONSERVATION DIVISION**  
Wichita, Kansas