

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


15.009.00775.0000

Company - ROBERT L. WILLIAMS et al
Farm - Senko No. 2

SEC. 19 T. 20S R. 11W
SE SW SW

Total Depth. 3390
Comm. 7-8-48 Comp. 7-17-48
Shot or Treated.
Contractor. J. D. Ferrell Drig. Co., Inc.
Issued. 8-21-48

County. Barton
KANSAS



CASING: 250' 8 5/8" cem. w/150 sax.
Cement circulated.

Elevation. _____

Production. Dry

Figures Indicate Bottom of Formations.

cellar	4
sand	190
shale & shells	520
red bed	570
anhydrite	590
red bed & shells	940
shale & shells	1080
salt & shale	1240
shale & shells	1445
sand	1460
limo & shale	1515
lime	1620
broken lime	1780
lime	1857
lime & shale	2325
shale & shells	2490
shale & lime	2595
broken lime	2620
shale	2705
broken lime	2865
lime	2885
lime & shale	2990
broken lime & shale	3085
limo & shale	3150
lime	3370
conglomerate	3390

Total Depth ~~3390~~
3418

Tops:	
anhydrite	570
Topeka	2712
Heebner	2970
Brown Limo	3103
Lans.-K.C.	3123
Base K.C.	3309
Conglomerate	3349

RECEIVED
Conservation Dept.
JAN 26 1949
STATE CORPORATION
COMMISSION
KANSAS

PLUGGING
FILE SEC. 19 T. 20S R. 11W
BOX PAGE 74 LINE 38