


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Building Building  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Barton County, Sec. 21 Twp. 20 Rge. 11 (W) (NW)  
Location as "NE/CNW/SW" or footage from lines NW NW NW  
Lease Owner Isern Drilling Company  
Lease Name Meggers #1 Well No. 1  
Office Address Box 45, Ellinwood, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed April 28, 1954 19  
Application for plugging filed May 1, 1954 19  
Application for plugging approved May 1, 1954 19  
Plugging commenced May 1, 1954 19  
Plugging completed May 8, 1954 19  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Warren Horner  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3291 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	260'	None
				5-1/2"	3323'	2735'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with sand from 3291' to 3270' and ran 5 sacks of cement. Pumped in 60 barrels of mud and set a 14' rock bridge at 200'. Ran 8 sacks of cement at 186' and left set. Could not bail hole dry so ran 3' of sand on cement and then ran 14 sacks of cement. Bailed hole dry and mudded hole. Ran 6 sacks of cement, mudded hole to 30', set a 10' rock bridge and ran 10 sacks of cement on top. Plugging completed

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company  
Address Chase, Kansas

STATE OF KANSAS COUNTY OF BARTON  
I. M. M. Shropshire (employee of owner) or (owner/operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) I. M. M. Shropshire  
Lyons, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 17th day of May, 1954

My commission expires Feb. 10, 1955.

George A. Meyer Notary Public.

**PLUGGING**  
FILED SEC 21 T 20 R 11W  
BOOK PAGE 31 LINE 36

**RECEIVED**  
CORPORATION COMMISSION

MAY 13 1954

CONSERVATION DIVISION  
Wichita, Kansas

5-18-1954

WELL LOG

Isern Drilling Company etal, Owner - Meggers #1  
NW/4 NW/4 NW/4 Section 21, Township 20, Range 11W,  
Barton County, Kansas

ELEVATION: 1773 DF

Figures indicate bottom of formation  
0 to 105 sand

PIPE RECORD:

8-5/8" set at 260'  
5 1/2" set at 3323'

220 shale  
300 Red Rock  
508 Red Bed  
536 Anhydrite  
995 shale & shells  
1290 salt  
1500 shale & shells  
1698 lime & shale  
1730 sand  
2050 lime & shale  
2660 shale & shells  
2928 lime & shale  
2931 Heebner  
3025 lime & shale  
3054 shale & shells  
3098 lime  
3200 lime & shale  
3275 lime  
3323 lime & shale  
3327 Arbuckle  
3327 Total Rotary Depth

TOPS: RBM

Heebner 2927  
Toronto 2942  
Base Oread 2959  
Brown Lime 3054  
Lansing 3072  
Arbuckle 3320

Rotary Commenced 4-13-54  
Completed 4-21-54

CABLE TOOL WORK

Cable Tools Commenced 4-24-54  
Cable Tools Completed 4-28-54

Moved in cable tools. Drilled new hole from 3327 to 3350. Plugged well back to 3317. Perforated with 23 holes from 3295-3283 1/2. Acidized with 1000 gallons acid. Tore down.

STATE OF KANSAS )  
COUNTY OF BARTON ) ss

I, M. M. Shropshire, Drilling Superintendent of the above-described well, bring first duly sworn on oath, declare: That I have knowledge of the facts, statements and matters herein contained pertaining to the log of the above-described well, as filed, and that the same are true and correct. STATE CORPORATION COMMISSION

MAY 10 1954

M. M. Shropshire

CONSERVATION DIVISION

**PLUGGING**  
FILE SEC 21-20-11W  
BOOK PAGE 31-36

and Sworn to before me this 12th day of May, 1954.

George A. Meyer  
Notary Public

My Commission Expires Feb. 10, 1955.