


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15.009.14635.0000

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barton County, Sec. 22 Twp. 20 Rge. 11 (E) W (W)
Location as "NE/CNW&SW&" or footage from lines NE/4
Lease Owner West Supply Co., Inc.
Lease Name Fiege #1 Well No.
Office Address Chase, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 11-4-59 19
Plugging completed 11-14-59 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Don Truan
Producing formation Depth to top Bottom Total Depth of Well 3295 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	144'	none
				5-1/2"	3295'n	2637'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked the hole to 3300' and found it open.
Filled w/sand to 3280' and dumped 5 sacks of
cement with bailer. Pulled 5 1/2" casing.
Cleared hole and checked fluid to 30' and
mud to 150'. Mudded to 145', set rock bridge
to 135' and dumped 10 xsacks of cement with
bailer. Left set overnight. Bailed fluid to
120' and dumped 15 more sacks of cement.
Mudded the hole to 40', set rock bridge to
30' and ran 10 sacks of cement to base of
cellar.

11-18-1959

PLUGGING COMPLETED

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Knight Casing Pulling Co.
Address Chase, Kansas

RECEIVED
STATE CORPORATION COMMISSION
NOV 18 1959
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.
I, Noel J. Knight (employee of owner) or (owner) of the above-described
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 17th day of November, 19 59

Thomas V. Dwyer
Notary Public.

My commission expires 9-27-62

15.009.14635.0000

M. F. BEAR
Consultant Geologist
 809 CENTRAL BUILDING
 WICHITA, KANSAS

Keyes Drilling Company
 #1 Fliege NE Cor. 22-20-11W
 Barton County, Elev. 1762

Measurements taken from Rotary bushing which is 3 feet above derrick floor.

2600 - 2629	Gray and red shale, with some micaceous sand.
2745	lt. gray tan lime Topeka
2775	white lime with lt. gray chert
2847	tan lime
2850	dark gray to black shale
2855	gray shale
2873	tan dense lime
2878	gray green shale
2889	lt. tan lime
2893	brown black Heebner shale
2901	lt. tan lime
2909	gray, gray green and red shale
2923	lt. tan to clear lime, Base Oread
3019	red and gray to gray-green shale
3026	Brown dense lime
3035	red and gray shale
3125	lt. tan dense lime
(3147)	med. soft to soft white oolitic to oolitic porous lime, Drillers report no odor. However some of oolitic porous lime shows fair to good oil sat.
3170	tan platy lime
3200	med. tan platy lime
3214	tan lime
3222	med. soft white to clear lime, slightly Xlyn texture few pcs. show slight stain, no good porosity.
3278	tan dense lime
3288	gray to gray green shale
3291	tan lime
3293	gray to gray green shale
3298	white dense hard dolomitic pred., few pcs. clear chert some asphalt in dolomite, no stain or odor in top 2 ft., few pcs. show slight stain and had slight odor in last 3 feet drilled. Porosity dense to slightly Xlyn.

Tops Corrected to Derrick Floor:

Topeka 2626	Heebner 2886
Base Oread 2920	Brown lime 3016 da -1254
Lansing 3032 da -1270	
Med. soft oolitic to oolitic porous lime 3122-44	
Drillers reported no odor, however in dry samples some oolitic porous lime shows fair to good saturated. Zone from 3122 to 3130 may be worthy of testing before abandoning well.	
Top Arbuckle 3290 da -1528	
Some dead oil asphalt in top 2 ft., few pcs show slight stain in last 3 ft. drilled, slight odor, dolomite is dense.	

RECEIVED
 STATE CORPORATION COMMISSION

OCT 26 1959

CONSERVATION DIVISION
 Wichita, Kansas

Keyes Drilling Co.

#1 Flago NE Cor. 22-20-11W Barton Co., Elev. 1762

DATE	TO	NUMBER	REMARKS
2600	2610	4-4-3-3-4-3-3-3-3-3	
	2620	3-2-3-3-3-3-2-2-2-3	
	2630	3-3-2-2-2-3-2-3-5-9	
	2640	7-8-8-9-7-5-5-7-7-5	
	2650	6-6-5-6-7-8-9-8-8-9	
	2660	8-7-7-7-7-8-8-8-7-6	
	2670	6-4-4-4-4-4-4-5-4-6	
	2680	6-6-7-8-8-9-9-8-9-11	
	2690	12-12-11-9-9-8-8-8-9-7	
2690	2700	7-8-9-9-7-7-7-8-7-7	
2700	2710	8-9-8-8-9-11-13-5-5-5	
	2720	2-3-5-4-3-4-3-4-6-6	
	2730	5-6-4-4-5-8-8-4-3-4	
	2740	4-5-4-4-5-6-6-7-8-4	
	2750	3-3-3-4-5-6-6-7-8-7	
	2760	7-6-6-7-8-8-7-6-7-6	
	2770	7-7-5-6-5-5-6-7-7-7	
	2780	7-6-7-7-7-7-7-7-6-6	
	2790	7-7-6-5-4-4-4-5-4-3	
2790	2800	2-2-2-2-3-3-3-3-3-3	
2800	2810	4-6-7-7-5-4-3-2-2-2	
	2820	2-3-4-4-4-5-5-7-8-7	
	2830	4-5-5-5-5-5-5-7-7-8	
	2840	9-8-8-10-8-5-6-8-8-7	
	2850	7-8-9-9-9-8-4-4-5	
	2860	6-6-6-5-6-7-7-8-8-8	
	2870	8-9-10-9-9-8-10-10-11-9	
	2880	8-10-10-8-8-7-6-7-8-8	
	2890	8-8-7-5-5-5-5-6-6-5	
2890	2900	6-6-5-6-7-7-8-9-8-8	
2900	2910	9-7-8-7-7-6-7-7-7-8	
	2920	7-7-7-8-7-5-3-7-6-8	
	2930	7-7-6-5-4-5-5-5-5-6	
	2940	5-5-5-6-5-6-6-4-3-8	
	2950	5-5-6-5-3-4-4-4-6-6	
	2960	7-4-4-5-5-5-5-5-5-5	
	2970	5-5-5-4-5-5-5-5-5-5	
	2980	4-5-5-3-4-5-5-4-4-5	
	2990	5-4-6-4-4-5-5-5-5-6	
2990	3000	5-6-6-6-3-6-4-6-6-5	
3000	3010	6-5-5-5-5-4-4-4-5-6	
	3020	6-5-5-5-6-6-7-6-6-8	
	3030	9-11-11-6-6-6-6-6-6	
	3040	6-5-4-5-8-8-7-8-7-8	
	3050	8-7-6-6-5-9-9-10-6-6	
	3060	6-7-6-8-10-10-9-10-10-11	
	3070	10-9-8-6-6-6-9-8-8-7	

Page #2

Kayes Dalg Co #1 Pledge NK Cor.
22-20-11W, Barton Co., Elev. 1762

FROM	TO	MINUTES	REMARKS
3070	3080	7-7-8-8-7-8-11-7-9-10	
	3090	10-10-10-10-8-7-7-10-10-10	
	3100	11-11-10-7-7-8-7-8-8-7	
3100	3110	7-9-10-10-10-9-8-10-9-9	
	3120	11-11-7-6-6-7-10-11-10-10	
	3130	10-11-13-6-5-3-2-2-2-2	
	3140	4-3-3-5-5-4-3-4-3-4	3135 Circ.
	3150	3-3-3-4-3-3-3-4-4-6	
	3160	4-4-4-3-3-6-4-5-5-4	
	3170	5-6-4-4-4-6-9-7-6-7	
	3180	7-7-7-6-5-4-5-5-5-7	
	3190	7-5-4-5-6-7-6-6-6-6	
3190	3200	5-5-4-5-6-6-6-6-5-7	
3200	3210	6-5-6-7-7-7-6-7-7-6	
	3220	6-5-5-4-3-4-4-3-3-3	
	3230	3-3-4-6-7-7-5-6-7-6	
	3240	6-6-6-6-7-8-8-7-7-7	
	3250	7-7-8-5-5-5-6-7-6-5	
	3260	5-5-6-6-7-7-7-9-8-8	
	3270	8-9-9-9-8-6-7-8-7-7	
	3280	6-6-7-7-7-8-6-6-7-9	
	3290	8-6-5-6-7-8-8-8-7-6	
3290	3300	6-7-7-6-6-5-5-5	3295 Circ. 1 hr. 15 min. 3298 Circ.

Trip 3123