

4-032195

10-29

API Number: 15-009-20,503.0000

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

W2 NE NE /4 SEC. 19, 20, 11 W
4620 feet from S section line
990 feet from E section line

Operator license# 6569

Lease: Spece Well # 1

Operator: Carmen Schmitt, Inc.

County: Barton

Address: P.O. Box 47
Great Bend, Kansas 67530

Well total depth 3343 108.64 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 216 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: D.S. & W. Well Servicing, Inc. License# 6901

Address: Claflin, Kansas 67525

Company to plug at: Hour: A.M. Day: 29 Month: October Year: 1996

Plugging proposal received from: Clark

Company: D.S. & W. Well Servicing, Inc. Phone:

Were: Order 190 sxs 60/40 pozmix - 10% gel - 300# hulls. 12-7-1996

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 11:30 A.M., Day: 29, Month: October, Year: 1996

Actual plugging report: 8 5/8" set at 216' w/225 sxs. 5 1/2" set at 3341' with 100 sxs.
Prod. Perf. 3297' - 3311'. Ran tubing to 1250' circulated with 130 sxs cement with 300#
hulls mixed in. Pulled tubing and topped off with 10 sxs cement. Squeezed backside with 50
sxs cement to Max. P.S.I. 300#. Plug complete.

Remarks:

Condition of casing(in hole): GOOD BAD Any plug: YES X NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING. Elevation: GL

did not [X] observe the plugging.

Carl Goodrow
(agent)

Form CP-2/3

INVOICED

DATE DEC 31 1996

INV. NO. 47192