

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-20802-00-00
Spot: CNENWSE Sec/Twnshp/Rge: 22-20S-11W
1650 feet from S Section Line, 1650 feet from E Section Line
Lease/Unit Name: SCHULTE Well Number: 2
County: BARTON Total Vertical Depth: 3440 feet

Operator License No.: 101
Op Name: KCC FEE FUND
Address: 130 S. MARKET, ROOM 2078
WICHITA, KS 67202

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 261
Production: Size 4.5 feet: 3375
Liner: Size feet:

Well Type: SWD UIC Docket No: Date/Time to Plug: 05/03/2001 6:00 PM
Plug Co. License No.: 31826 Plug Co. Name: T&C MFG. & OPERATING, INC.
Proposal Rcvd. from: CRAIG PANGBURN Company: T&C MFG. & OPERATING, INC. Phone: (316) 793-3911

Proposed Ordered out 300 sxs 60/40 pozmix - 10% gel - 500# hulls.
Plugging Well used as an illegal disposal.
Method: Disposing down casing.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 05/03/2001 8:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

May 01, 2001 - Drilled out well to 1500'.
May 02, 2001 - Hole collapsed.
May 03, 2001 - Drilled down to 1200'.
Ran tubing to 2000' - decided to P&A.
Tied onto and pumped 50 sxs cement.
Pulled up to 1000' and pumped 50 sxs cement.
Pulled up to 500' and pumped 165 sxs cement.
Topped off with 20 sxs.

RECEIVED
KANSAS CORPORATION COMMISSION
MAY 16 2001
5-16-2001
CONSERVATION DIVISION

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Jay Pfeifer

(TECHNICIAN)

BOB

