

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-19022-00-01
Spot: NESESE Sec/Twnshp/Rge: 22-20S-11W
990 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: SCHULTE Well Number: 4
County: BARTON Total Vertical Depth: 3292 feet

Operator License No.: 101
Op Name: KCC FEE FUND
Address: 130 S. MARKET ROOM 2078
WICHITA, KS 67202

Conductor Pipe: Size _____ feet:
Surface Casing: Size 10.75 feet: 188
Production: Size 7 feet: 3039
Liner: Size 4.5 feet: 3104

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/02/2001 3:00 PM
Plug Co. License No.: 31826 Plug Co. Name: T&C MFG. & OPERATING, INC.
Proposal Rcvd. from: CRAIG PANGBURN Company: T&C MFG. & OPERATING, INC. Phone: (316) 793-5483

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 500# hulls.
Plugged January 21, 1969 - pulled 1985' of 7" out of Dannebohm #2.
Washed down June 17, 1975.
Fluid Level 670'.

Plugging Proposal Received By: JAY PFEIFER WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 05/02/2001 4:45 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 530' and 1550'.
Tied onto 4 1/2" and pumped 200 sxs and 400# hulls.
Max. P.S.I. 300#. S.I.P. 300#.
Hooked onto casing annulus and pumped 50 sxs and 100# hulls.
Max. P.S.I. 300#. S.I.P. 200#.

RECEIVED
KANSAS CORPORATION COMMISSION
MAY 10 2001
5-10-2001
CONSERVATION DIVISION

Remarks: ORIGINAL LEASE KNOWN AS DANNEBOHN #2. ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Jay Pfeifer
(TECHNICIAN)

MAY 04 2001

M-P PETROL., INC.
BOX 402, RUSSELL, KS.
CONTR CO. TOOLS

"OWWO"
#4 SCHULTE
CTY BARTON

22-20-11W
NE SE SE

39

GEOL


FIELD CHASE-SILICA

E 1763

CM 6/17/75 ^{CAND} ISSUED 3/30/78

IP OIL WELL

INTERVAL NOT
RELEASED



SMP	TOPS	DEPTH	DATUM
ANH		495	+1268
TOP		2630	- 867
HEEB		2891	-1128
B OREAD		2926	-1163
BR LM		3015	-1252
LANS		3033	-1270
DOUG SD		3050	-1287
TD		3292	-1529

OLD INFO: WAS W.L. HARTMAN #2 DUNNEBOHN
SPD 3/11/49, 35 BOPD; 8" 162, 5" 3909
PERF 12/3053-57 PERF 24/3063-67; ACID
1000 PUMP 35 BOPD

NEW INFO: WSH DWN TO 3105', CO TO
3292', SET 4 1/2" 3104', NO OTHER INFO
IS AVAILABLE ON THIS WELL

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

W. L. HARTMAN

#2

DUNNEBOHN

22-20-11W
NE SE SE

Contr. H. & H. DRILLING COMPANY

BARTON

County

E 1763

Comm 3-11-49

Comp. 4-15-49

IP 35 BOPD

Tops	Depth	Datum
ANH	495	
TOP	2630	
HEEB	2891	
B/OREAD	2926	
BR LM	3015	
LANS	3033	
DOUG SD	3050	
	3292	

Casing

8" 162

5" 3090

Perf 12-3 3053-57 perf

24-3 3063-67; Acid 1000

Pump 35 BOPD