

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-14158-00-01
Spot: NENESE Sec/Twnshp/Rge: 22-20S-11W
330 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: SCHULTE Well Number: 5
County: BARTON Total Vertical Depth: 3312 feet

Operator License No.: 101
Op Name: KCC FEE FUND
Address: 130 S. MARKET, ROOM 2078
WICHITA, KS 67202

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 123
Production: Size 5.5 feet: 3304
Liner: Size 4.5 feet: 3302

Well Type: OIL UIC Docket No: Date/Time to Plug: 05/04/2001 1:00 PM
Plug Co. License No.: 31826 Plug Co. Name: T&C MFG. & OPERATING, INC.
Proposal Rcvd. from: CRAIG PANGBURN Company: T&C MFG. & OPERATING, INC. Phone: (316) 793-3911

Proposed Ordered out 250 sxs 60/40 pozmix - 10% gel.
Plugging Originally plugged as the Dannebohm #4 September 16, 1965 - pulled 2858' of 5 1/2".
Method: Wash down June 20, 1975.

Plugging Proposal Received By: JAY PFEIFER Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 05/04/2001 3:15 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 530' and 1550'.
R.I.H. tubing to 1500'.
Tied onto and pumped 80 sxs and 400# hulls.
Pulled up to 150'.
Tied onto and circulated cement up casing and annulus with 75 sxs.
POOH tubing.
Tied onto 5 1/2" and pumped to pressure with 50 sxs.
Max. P.S.I. 120#. S.I.P. 0#.

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 17 2001
5-17-2001
CONSERVATION DIVISION

Bob

Remarks: LEASE ALSO KNOWN AS THE DANNEBOHM #4. ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Jay Pfeifer

(TECHNICIAN)

MAY 15 2001

SILICA POOL