

State of Kansas



15.009.14625.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

NOV 28 1966

11-28-1966  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Roy Pool of F. G. Holl has this

date requested permission to plug the following described well:

Mr. F. G. Holl guarantees payment of the plugging fee.

Operator's full Name: F. G. Holl

Complete Address: 6427 E. Kellogg, Wichita, Kansas

Lease Name: Hagen Well No. # 1

Location: NE NE NE Sec. 21 Twp. 20 Rge. 11 (E)(W) W

County Barton Total Depth 3340 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Roy Pool was instructed to plug the well as follows:

8 5/8" 277' Cwc.

Set bottom plug @ 3010' & dumped 5 sax cement with dump bailer.

Pulled pipe. Bailed hole dry to 250', set 10' rock bridge, &

displaced 25 sax cement. Mud to 40', set rock bridge, & displaced

10 sax cement, cementing to base of cellar.

Very truly yours,

*Don Truman*  
Conservation Division Agent