

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plugging  
of formations.

Barton County, Sec. 12 Twp. 20 Rge. (E) 12 (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines NE NE NE

Lease Owner C. E. Ash et al

Lease Name P Schartz C Well No. 3

Office Address 309 Petroleum Building; Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed August 9 1944

Application for plugging filed August 8 1944

Application for plugging approved August 8 1944

Plugging commenced August 8 1944

Plugging completed August 9 1944

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Elden Pettie

Producing formation Arbuckle Lime Depth to top 3350 Bottom 3383 Total Depth of Well 3383 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle Lime	Water	3350	3383	8 5/8	322	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded with Rotary. 10 1/2# Mud put in by pump to 315 ft.  
Set wood plug at 315 ft. 15 ft. rock 15 sacks cement  
Mudded to 36 ft. Set wood plug at 36 ft. 5 ft. rock  
10 sacks cement. Filled to top with dirt.

PLUGGING  
FILE # 12 2012W  
BOOK PAGE 127 SE 28

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to C. E. Ash  
Address 309 Petroleum Building; Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
I, C. E. Ash, (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. E. Ash 8-22-44  
309 Petroleum Bldg; Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 9 day of August, 1944

My commission expires September 10, 1947  
Notary Public.

C. E. ASH et al

P. Schartz G3  
NE NE NE Sec. 12-20-12W  
Barton County, Kansas

Comm. Rig Up : 7-23-44	Elevation :
Comm. Drlg. : 7-26-44	Initial Prod. : Dry & A
Completed : 8-9-44	Contractor : C.E. Ash
Total Depth : 3383'	Tools : Rotary

CASING RECORD

<u>Run</u>	<u>Pulled</u>	<u>Left In</u>
322'- 8 5/8" Surface		322'- 8 5/8" Surface

<u>STRATA</u>	<u>DEPTH</u>
Sand	85
Shale & Shells	320
Shale	325
Red Rock	550
Anhydrate Lime	575
Shale	712
Shale & Shells	1045
Salt	1310
Shale & Shells	1485
Lime	1560
Shale & Lime	2030
Lime	2070
Shale	2095
Lime & Shale	2390
Lime	2420
Shale & Lime	2725
Lime	2980
Shale	3065
Lime	3343
Cong	3350
Sil Lime	3383
Total Depth	3383

TOPS

Brown Lime	3065
KC or White Lime	3084
Conglomerate	3343
Silicious Lime	3350

**PLUGGING**  
FILE 12 20R12W  
BOOK PAGE 127 LINE-28

I hereby certify that the above is the true and correct log of said well as reflected by the daily drilling reports.

C. E. ASH

Subscribed in my presence and sworn to before me this 9th day of August, 1944.

Notary Public in and for Sedgwick County, Kansas.

My commission expires September 10, 1947

