

STATE OF KANSAS
STATE CORPORATION COMMISSION
260 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15.009-07204.0000
API NUMBER None

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE NAME Schartz C
WELL NUMBER 5

1980 Ft. from S Section Line
990 Ft. from E Section Line

SEC. 12 TWP. 20S RGE. 12 (E) or (W)
COUNTY Barton

Date Well Completed 9-20-48

Plugging Commenced 8-18-87

Plugging Completed 8-18-87

LEASE OPERATOR Kaiser-Francis Oil Company

ADDRESS P. O. Box 21468, Tulsa, OK 74121-1468

PHONE# (918) 494-0000 OPERATORS' LICENSE NO. 6568

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well).

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dist. 4, Hays, KS

Is ACO-1 filed? on old form if not, is well log attached? -

Producing Formation Arbuckle Depth to Top 3337 Bottom 3345 T.D. 3345

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	Oil	3337	45	8-5/8	337	-0-
				5-1/2	3337	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pumped 150 sxs thrifty-mix + 5 sxs hulls from TD to surface. Pumped add'l 50 sxs cmt down annulus.

JOB COMPLETE

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kaiser-Francis Oil Company License No. 6568

Address P. O. Box 21468, Tulsa, OK 74121-1468

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Charlotte Van Valkenburg (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) C. Van Valkenburg
(Address) P. O. Box 21468, Tulsa, OK 74121

SUBSCRIBED AND SWORN TO before me this 24th day of August, 19 87

Deborah L. Harrell
Notary Public

My Commission Expires: 12-6-89

RECEIVED
STATE CORPORATION COMMISSION Form CP-
Revised 08-84

8-27-87 AUG 27 1987

Fraser - Ash Co.

15.009.07204.0000

C. E. ASH et al

Schartz "C" # 5
CW $\frac{1}{2}$ NE SE Sec. 12-20-12W
Barton County, Kansas

Comm. Rig Up : 7-14-1948
Comm. Drilling: 9-1 -1948
Comp. Rotary : 9-14-1948
Completed : 9-20-1948

Elevation : 1787 (card)
Initial Prod.: 300 bbl.
Contractor : C. E. Ash
Tools : Rotary

CASING RECORD

Run		<u>Pulled</u>		<u>Left In</u>
337'	8 5/8"	(Cem. w/170 sax)	337'	8 5/8"
3337'	5 1/2"	(Cem. w/100 sax)	3337'	5 1/2"

STRATA DEPTH

Sand	100
Red bed	280
Shale blue	300
Red bed	565
Anhydrite lime	615
Shale & shells	1060
Salt	1200
Shale & shells	1430
Lime	1500
Shale	1700
Lime	1800
Shale & lime shells	1950
Lime	2055
Shale	2385
Lime & shale	2555
Lime	2630
Lime & shale	2745
Lime	2875
Lime & shale	2905
Lime	2960
Lime & shale	3110
Lime	3345
Total Depth	3345

TOPS: R. B.

Brown lime	3073'
KC or White lime	3094
Base /KC lime	3330
Conglomerate	none
Arbuckle lime	3335 (-1548)

*3094
1787
-1307*

When hole was cleaned out to bottom of Rotary hole of 3341' (-1554) the hole filled 2550' with oil and no water in 12 hrs.

Showed more oil 3341'-3343' (-1554-56)
Probably more oil 3343'-3345' (-1556-58) TD
Swabbed 13 bbls. oil per hr. for 3 hrs. no water.
Est. 300 bbls. per day.

*10' art. penetrated
prod 8' open hole.*

RECEIVED
STATE CORPORATION COMMISSION

JUN 22 1987

CONSERVATION DIVISION
Wichita, Kansas