

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15.009.00279.0000

API NUMBER Completed 12-14-58

LEASE NAME Schartz "D"

WELL NUMBER 1

2310 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 12 TWP. 20S RGE. 12 XXX (W)

COUNTY Barton

Date Well Completed 12-14-58

Plugging Commenced 4-6-94

Plugging Completed 4-6-94

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Mustang Oil & Gas Corporation

ADDRESS 100 S. Main, Suite 300, Wichita, KS 67202

PHONE#(316) 267-8011 OPERATORS LICENSE NO. 5652

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-5-94 (date)

by Bruce Basye (District #4) (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? _____

Producing Formation Arbuckle Depth to Top 3342 Bottom 3348 T.D. 3354'
PBTD 3010' CIBP

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	190'	None
				5-1/2"	3346'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
SEE BACK

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Mustang Oil & Gas Corporation * License No. 5652

Address 100 S. Main, Suite 300, Wichita, KS 67202 *Service Company: Allied Cementing

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mustang Oil & Gas Corporation

STATE OF Kansas COUNTY OF Sedgwick, ss.

Wayne L. Brinegar, Exploitation/Production Mgr. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Wayne L. Brinegar

(Address) 100 S. Main, Suite 300, Wichita, KS 67202



SWORN TO before me this 7th day of April, 19 94

Patricia A. Reilley Notary Public
RECEIVED
STATE CORPORATION COMMISSION

My Commission Expires: August 11, 1995

cc: District #4 - Bruce Basye

4-11-94

APR 11 1994
Form CP-4
Revised 05-88
CONSERVATION DIVISION

Schartz "D" #1 - Plugging Procedure

Perforated 5½" casing w/2 shots @240'; 2 shots @572' and 2 shots @1375'.
Ran tubing and plugged as follows:

90 sxs 60/40 Pozmix (10% gel) w/100# hulls @2960'
90 sxs 60/40 Pozmix (10% gel) w/100# hulls @1960'
100 sxs 60/40 Pozmix (10% gel) w/300# hulls @960'
40 sxs 60/40 Pozmix (10% gel) @430' and circulated cement to surface

Hooked to 5½" casing, pumped 10 sxs & press'd to 100#; SI @50#
Pumped 3 sxs down backside & press'd to 200#; SI @50#.

Job complete @3:35 pm 4-6-94.

Witnessed by KCC District #4 Rep Bruce Bayse

D
ALPINE'S MINE SCHARTZ NO. 1
NW NW SW Sec. 12-20S-12W
Barton County, Kansas

Elevation 1797 KMA KB

12-8-56 Set 8 5/8" at 190 feet with 200 sacks
job completed at 6 P. M.
12-9-56 1582
12-10-56 2050
12-11-56 2580
12-12-56 2885
12-13-56 3145
12-14-56 3348 RTD

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 3 1954

Anhydrite	572 /1225
Heelmer	2960 -1163
Brown Line	3062 -1285
Lansing	3100 -1313
Base of Kans. City	3333 -1536
Artuckle	3344 -1547
5 1/2" Casing	3346 with 125 sacks
RTD	3348 -1551

CONSERVATION DIVISION
WICHITA, KS

DRILLIN IN INFORMATION

12-16-58 Moved in - rigged up
12-17-58 Swabbed to plug - drilled plug, float, cement
shoe - cleaned to RTD 2' under $8\frac{1}{2}$ "
12-18-58 Fill up 200 feet - drilled 3348 to 3354
Total depth - bailer test 2.84 bbls per hour
oil level gained while bailing 125 feet
12-19-58 1100 fill up this A. M. - 10 gal water
Swabbed 28 bbls to bottom - hourly sand test
for 7 hours - 2 bbls per hour.
12-20-58 1100 ft. fill up - tearing down swab equip
ran tubing and rods - tearing down
12-22-58 Moved off
12-26-58 On production.

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 31 1994

CONSERVATION DIVISION
WICHITA, KS