

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-049-21865-00-00
Spot: SWSESESE Sec/Twnshp/Rge: 21-29S-9E
273 feet from S Section Line, 632 feet from E Section Line
Lease Name: SMITH B Well #: 10
County: ELK Total Vertical Depth: 2450 feet

Operator License No.: 32874
Op Name: VEEM JADE OIL & GAS LLC
Address: 11417 S GRANITE AVE
TULSA, OK 74137

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2450		100 SX
SURF	8.625	60		20 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/10/2018 12:00 PM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: KEVIN WARDLOW Company: _____ Phone: (620) 330-3666

Proposed Plugging Method: 20 sacs cement at bottom. Set intermediate Plug 20 sacs. 300 to surface, Set Gel spacers between cement plugs. Perforate 300 foot and intermediate where ever State recommends. 60/40 poz cement with 4% gel

Plugging Proposal Received By: DUANE SIMS WitnessType: NONE
Date/Time Plugging Completed: 05/10/2018 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Casing was perforated at 500'. Washed 2" to 1740' and hit something solid like a bridge plug. Pulled up to 1730' gelled hole and spotted 15 sack plug. Pulled up to 1093' and spotted 10 sack plug. Pulled up to 507' and circulated cement to surface. Pulled 2" and topped well off. A total of 152 sacks of 60/40 pozmix with 4% gel were used to plug this well.

Perfs:

RECEIVED
KCC DIST # 3
JUN 06 2018
CHANUTE, KS

DS


INVOICED
JUL 19 2018

Remarks: WELL WAS PLUG DUE TO FAILED CIT.

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)