

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-155-20664-00-00  
Spot: SENWSE Sec/Twnshp/Rge: 15-25S-6W  
1650 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: ELWARD Well #: 2  
County: RENO Total Vertical Depth: 3555 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 1700 WATERFRONT PKWY BLDG 500  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3554	1184	100 SX
SURF	8.625	264		200 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/17/2018 12:00 AM  
Plug Co. License No.: 32983 Plug Co. Name: STEVE'S WELL SERVICE, INC.  
Proposal Rcvd. from: TRACY BLACK Company: \_\_\_\_\_ Phone: (316) 215-1873

Proposed  
Plugging  
Method:

AS PER KCC RULES & REGS


Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL  
Date/Time Plugging Completed: 04/17/2018 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

CIBP SET @ 3448' W/2 SKS CEMENT ON TOP, 4 1/2" CASING SHOT OFF @ 1184' AND REMOVED. TTIH PUMPED 10 SKS GEL, AND 50 SKS CLASS A W/3% CC PLUG @ 900' TTOH, TAGGED @ 690', TTIH @ 300', PUMPED 120 SKS CLASS A WITH 2% CC TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3496	3504		

  
  
INVOICED  
JUL 19 2018

Remarks: QES #55336 TICKET # OUT OF EL DORADO - DENIED TA

Plugged through: TBG

District: 02

Signed

BJ Hope

(TECHNICIAN)

JK