

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-155-20897-00-00
Spot: NENWSENW Sec/Twnshp/Rge: 15-25S-6W
3680 feet from S Section Line, 3603 feet from E Section Line
Lease Name: ELWARD Well #: 3
County: RENO Total Vertical Depth: 4200 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4076	1752	150 SX
SURF	8.625	267		200 SX

Well Type: SWD UIC Docket No: D21654.0 Date/Time to Plug: 04/19/2018 12:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: TRACY BLACK Company: VESS OIL CORP Phone: (620) 672-9300

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 04/20/2018 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

CIBP SET @ 3890' W/2 SKS CEMENT ON TOP, 4 1/2" CASING SHOT OFF @ 1752' AND REMOVED. TTIH. QES PUMPED 10 SKS GEL, AND 50 SKS CLASS A W/3% CC PLUG @ 900'. TTOH TAGGED WITH WIRELINE @ 592', SET TUBING @ 325', PUMPED 120 SKS CLASS A W/2 % CC TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4076	4200		

SCANNED

INVOICED
JUL 19 2018

Remarks: QES #55339 OUT OF EL DORADO - DENIED TA

Plugged through: TBG

District: 02

Signed B. J. Hope

(TECHNICIAN)

✱