

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-015-19692-00-00  
Spot: NESWNE Sec/Twnshp/Rge: 14-26S-4E  
1650 feet from N Section Line, 1650 feet from E Section Line  
Lease Name: HAMILTON A Well #: 26  
County: BUTLER Total Vertical Depth: 2439 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 1700 WATERFRONT PKWY BLDG 500  
WICHITA, KS 67206

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD   | 5.5   | 2404       |             | 150 SX   |
| SURF   | 8.625 | 120        |             | 150 SX   |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/30/2018 12:00 AM  
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.  
Proposal Rcvd. from: SHANE SUMMERS Company: \_\_\_\_\_ Phone: (970) 618-3416

Proposed Plugging Method: Per KCC District #2 instructions

Plugging Proposal Received By: JONATHAN HILL Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/30/2018 12:00 AM KCC Agent: JONATHAN HILL

Actual Plugging Report:

4/30/2018:  
1) Dug out head -- cement at surface on backside of production casing from previous squeeze job (545'-0")  
2) Ran in tubing to 2400', pumped 50 sks Class A cement with 3% CaCl and 40 lbs of hulls. Good returns  
3) Pulled tubing out, wait 1.5 hrs, ran in hole with wireline and tagged plug at 1984'  
4) With hole loaded, MIT'd casing at 150 psi -- passed  
5) Ran in tubing to 311', pumped 60 sks of class A w/ 3% CaCl. Circulated cement to surface  
6) Pulled tubing out, topped off with 10 sks cement. Cement slowly falling. Shut down for day  
5/1/2018: Tagged plug at 15', hole topped off with 2 sks cement.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 2404 | 2439 |      |          |

**INVOICED**  
**JUL 19 2018**

Remarks: CEMENTING COMPLETED BY QES, EL DORADO, KS. TICKET #: 55398

Plugged through: TBG

District: 02

Signed [Signature] 4/11  
(TECHNICIAN)

[Handwritten mark]