

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-23025-00-00
Spot: NWSENE Sec/Twnshp/Rge: 9-22S-11W
948 feet from N Section Line, 370 feet from E Section Line
Lease Name: SLEEPER Well #: 3
County: STAFFORD Total Vertical Depth: 3590 feet

Operator License No.: 5420
Op Name: WHITE & ELLIS DRILLING, INC.
Address: 10500 E. BERKELEY SQUARE PKWY. S
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3400		WITH 2 SX CMT
CIBP		3545		
PROD	5.5	3584	2400	WITH 175 SX CMT
SURF	8.625	290		WITH 100 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/07/2018 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: SAND TO 3400' WITH 5 SX CMT. PLUG AT 600' WITH 12 SX GEL & 50 SX CMT. PLUG AT 310' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/07/2018 2:00 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

SET CIBP @ 3400' WITH 2 SX CMT PLACED ON TOP. 1ST PLUG AT 600' WITH 12 SX GEL & 50 SX CMT. FLUID CIRCULATED. 2ND PLUG AT 310' WITH 50 SX CMT. FLUID CIRCULATED. 3RD PLUG AT 40' & PUMP 20 SX CMT TO FILL HOLE TO SURFACE. CMT REMAINING AT SURFACE LEVEL.

Perfs:

Top	Bot	Thru	Comments
3512	3557		
3445	3451		

INVOICED
JUL 19 2018

Remarks: COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

District: 01

Signed Ken Scofield
(TECHNICIAN)

RECEIVED
JUN 13 2018
KCC DODGE CITY