

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-151-21620-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 35-26S-12W
363 feet from S Section Line, 4967 feet from E Section Line
Lease Name: GENE STUDER Well #: 1
County: PRATT Total Vertical Depth: 4600 feet

Operator License No.: 33856
Op Name: WHITE EXPLORATION, INC.
Address: 1635 N WATERFRONT PKWY STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4120		WITH 2 SX CMT
PROD	5.5	4599	1500	WITH 250 SX CMT
SURF	8.625	350		WITH 250 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 05/22/2018 8:30 AM
Plug Co. License No.: 35303 Plug Co. Name: DESTINY SERVICES LLC
Proposal Revd. from: TERRY BAIRD Company: WHITE EXPLORATION Phone: (316) 641-8906

Proposed Plugging Method: CIBP @ 4120' & 2 SX CMT. PLUG AT 700' WITH 10 SX GEL & 40 SX CMT. PLUG AT 380' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEN SCOFIELD WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/22/2018 10:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4120' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 683' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 389' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4162	4192		

INVOICED
JUL 19 2018

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed Stephan J. Pfeifer
(TECHNICIAN)

RECEIVED
MAY 25 2018
KCC DODGE CITY