

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-155-20728-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 13-23S-10W
2970 feet from S Section Line, 2310 feet from E Section Line
Lease Name: WEBER C Well #: 1
County: RENO Total Vertical Depth: 3700 feet

Operator License No.: 5141
Op Name: ZENITH DRILLING CORPORATION
Address: 1223 N ROCK ROAD BLDG A STE 200
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	3540		
PROD	4.5	3699	2209	125 SX
SURF	8.625	254		250 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/17/2018 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL
Date/Time Plugging Completed: 05/17/218 4:15 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, PULL RODS & TUBING. SET CIBP AT 3540' AND CAP WITH 4 SX'S CEMENT. CUT CASING OFF AT 2209' AND PULL TO 1450'. PUMP 15 SX'S GEL FOLLOWED BY 35 SX'S COMMON CEMENT WITH 3% CC. PULL CASING TO 800' AND WAIT 1.25 HRS. TAG CEMENT AT 1350' WITH SWAB BAR. PUMPED 35 SX'S COMMON WITH 3% CC AT 800'. PULLED CASING TO 300' AND PUMPED 175 SX'S GETTING CEMENT CIRCULATION TO SURFACE. PULLED CASING OUT AND TOPPED OFF.

Perfs:

Top	Bot	Thru	Comments
3592	3628		CSG

INVOICED
JUL 19 2018

SCANNED

Remarks: COPELAND CEMENT #46061.

Plugged through: CSG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

✓