

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-135-26005-00-00  
Spot: E2NWNESW Sec/Twnshp/Rge: 15-17S-21W  
2200 feet from S Section Line, 1950 feet from W Section Line  
Lease Name: CAMPIE Well #: 1-15  
County: NESS Total Vertical Depth: 4200 feet

Operator License No.: 35516  
Op Name: PHILLIPS OIL COMPANY, LLC  
Address: 650 E GILBERT  
WICHITA, KS 67211

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	302		WITH 225 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/02/2018 1:15 PM  
Plug Co. License No.: 34908 Plug Co. Name: SKYTOP DRILLING LLC  
Proposal Revd. from: MARVIN REIF Company: SKYTOP DRILLING LLC Phone: (785) 434-2028

Proposed Plugging Method: 1ST PLUG AT 1500' WITH 50 SX CMT. 2ND PLUG AT 780' WITH 80 SX CMT. 3RD PLUG AT 270' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE  
Date/Time Plugging Completed: 06/03/2018 3:00 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

1ST PLUG AT 1500' WITH 50 SX CMT. 2ND PLUG AT 780' WITH 80 SX CMT 3RD PLUG AT 270' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

**INVOICED**  
**JUL 19 2018**

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY COPELAND

Plugged through: DP

District: 01

Signed \_\_\_\_\_



(TECHNICIAN)

RECEIVED  
JUN 11 2018  
KCC DODGE CITY



SK